

NOVEL CELLULAR APPROACH TO GREENFIELD WIRELESS DEVICE NETWORKS - ALBA GAS STATION (AGS)







Bahrain Petroleum Company (BAPCO)

Advisory/Group




- State owned (erstwhile CALTEX) Oil & Gas Company engaged in Exploration, Refining, Storage, Marketing, Training & Development and Environmental initiatives in the Kingdom of Bahrain.
- Owns a 270,000 BOPD Refinery, over 14 million barrels of storage facilities, a Marketing terminal and a Marine terminal for transfer of petroleum products.
- ✤ 95% of the company's Refined products are exported.

✤ Refinery under going capacity expansion from 270,000 to 360,000 BOPD.





Major Automation Technology Milestones in Bapco



[©] ARC Advisory Group • 3

Bapc

دومــــا نـرتـقـــي

Empowering Progress

ISA

WIRELESS



ALBA GAS STATION (AGS)

- A new Gas Distribution Network Station designed to supply High Pressure Khuff Gas and Low Pressure Residue Gas to the upcoming Alba Line 6 Expansion.
- Comprises Gas Pre-conditioning Systems, Condensate Knock-out/Transfer Systems and Vent/Flare Management Systems.
- DESIGN OBJECTIVES
- Energy Optimization
- Low Utility Index
- Large Data Rates

Advisory/Group

- Reducing Capital Costs
- Infrastructure Foundation for Future Analytics




Anatomy of Innovation

ARC

Advisory Group






WIRELESS

Instrument Distribution

Advisory Group



WIRELESS



ALBA Gas Station Project



| Project Summary | |
|-----------------------------------|---------------|
| Internal Man hours | 14,600 |
| External Man hours | 19,100 |
| Packages (RFQs) | 15 |
| FDS / Technical Specifications | 16 |
| Vendor Documents / Drawings | 400 (approx.) |
| Instrument Loops (Total) | 400+ |

| Project Summary | |
|------------------------------------|-----------|
| Project budgeted cost | 13.17 MM |
| Actual cost | 8.0 MM |
| Saving | 5.17 MM |
| Total cost of the Project | 21 MM |
| Time to complete the Project | 18 Months |
| | |





Challenges



- Tight Project Schedule: 1 Year to complete and hand over
- Unmanned Station & Remote Location
- Process Controllers/Shutdown Systems Wide Area Remote Operation from Central Control Facility
- 100% Unit availability any upset is critical to the operation of the 1,792 MW Alba Power Plant affecting the Smelter operation.
- Unavailability of secure utilities like Power and Air.
- Surveillance Camera and communications in the Unit to enhance Security.
- **CTMS design to 100% compliance to 3rd Party Audit.**








© ARC Advisory Group • 8

Cellular Concept & Tagging – Device Wireless

ARC

Advisory Group





دومــــأ نـرتقـــى

Empowering Progress


VISION, EXPERIENCE, ANSWERS FOR INDUSTRY, INFRASTRUCTURE & CITIES

© ARC Advisory Group • 9

Cellular Concept for Small Packages - Device Wireless

ARC

Advisory Group





دومــــا نـرتقـــى

Empowering Progress


VISION, EXPERIENCE, ANSWERS FOR INDUSTRY, INFRASTRUCTURE & CITIES

© ARC Advisory Group • 10


P&ID Representation & Device Wireless Link Performance

Graphic Viewe Area001(101)

YFGW410 🔘 🖉



Redundant network snapshot



Network Performance

744-AT-0028


744-AT-002

Concurrent Domains for Process & Safety Instruments

UY-0001AB


- Link stable
- PER <10% (acceptable range)
- RSSI < -75dB
- System architected using Standard 5 meter poles





ARC

AGS Device Wireless Plot Plan and Layout






ا نـرتقــــى


WIRELESS

ALBA GAS STATION SYSTEM ARCHITECTURE



FUTURE READY INFRASTRUCTURE VISION, EXPERIENCE, ANSWERS FOR INDUSTRY, INFRASTRUCTURE & CITIES


SAFETY & RELIABILITY IN ENGINEERING DESIGN



VISION, EXPERIENCE, ANSWERS FOR INDUSTRY, INFRASTRUCTURE & CITIES

ARC

Advisory Group



Benefits & Performance Metrics



- Procurement Strategies to minimize lead time; Maximize Wireless instruments to save construction time.
- Remote control of the complete process & elimination of data mapping saving time.
- RTUs connected to Multi-level SCADAs with equalized FAST/TOOLS S/W and Triple redundant geospatial SCADA Servers.
- Early detection of dormant problems & remote maintenance of Systems via Unified converged networks.
- Improved Safety and Reliability through design.

Advisory/Group

- Reduced power consumption of devices (Current power consumption ~ 3KVA) and modular 10KVA/3KVA
 UPS for ease of maintenance & future expansion.
- **3** Cameras and 1 IP phone for surveillance and communication with future network capacity of 70 Cameras.
- 0.5 Class OIML R137-1 Ultrasonic Flow Meters (CTMS audited by Kelton, UK)

Redundant high speed (800 MBPS) Microwave Radios (18 GHz) with 1+1 configuration and path redundancy.
















ALBA GAS STATION





Custody Transfer Metering Skid







ALBA GAS STATION





Wireless Instruments for Pressure, Temperature and Position Indication



AGS Project Collaborators









Lessons Learned



- Deeper collaboration with Vendors required to meet objectives
- More engagement needed to improve local expertise
- Vendors need to be encouraged to align products to Industrial Ethernet and Digital Networking






DIGITAL INFRASTRUCTURE PERSPECTIVE



WIRELESS



VISION, EXPERIENCE, ANSWERS FOR INDUSTRY, INFRASTRUCTURE & CITIES

ARC

Advisory Group



Thank you



